

RECORD OF BID CLARIFICATION / AMENDMENT				
<b>Project</b>		<i>"Promotion of Youth Employment and Vocational Training in Kenya" (BMZ Reference Numbers: 2016 67 211 and 2016 65 298)</i>		
<b>Procurement name</b>		Supply, Delivery and Commissioning of Equipment for Technical Training Institutes in Kenya: ICT Hardware, Software, and Internet connectivity		
<b>Procurement ref. no.</b>		ICB-09/MOE-VTT/TVET/KfW 2016 67 211/003/2024-2025		
<b>Clarification No.</b>		4		
<b>Date of Clarification</b>				
<b>S/N</b>	<b>Question / Clarification Request</b>	<b>Date of Request</b>	<b>Purchaser's Response</b>	<b>Clarification / Amendment</b>
20	<p>Kindly clarify the number of users for the Accounting Application</p> <p>Software application should meet the financial/accounting needs of the TVET Institution. Should track sales, expenses and profits, create and send unlimited invoices, track and manage tax including VAT, works on PC, MAC and Mobile, manage and pay bills, transact in multiple currencies, generate sales quotes, track inventory, create purchase orders, track project or job probability and recurring transactions; manage budgets.</p> <p>Question –</p>	01.04.2025	The number of licenses is mentioned in the bidding document.	Clarification

	<p>1.How many concurrent users will be using the platform at any time?</p> <p>2.Is the solution on premise, cloud or hybrid</p> <p>3.Will the solution be deployed in the 3 institutions?</p>		<p>Q1. Each institution has its independent number of licenses. Please refer to the bidding document.</p> <p>Q2. The application shall be On Premise.</p> <p>Q3. Yes. The application shall be installed at all 3 institutes.</p>	
21	<p>The bid security and liquidity letter from the bank.</p> <p>Kindly confirm whether these documents can be issued by two different banks or if they must come from the same bank.</p>	01.04.2025	Different Institutions can issue the referenced documents.	Clarification
22	<p>"7.0 Structured Cabling</p> <p>A Metal trunking of 200mm by 50mm dimensions must be installed. One will be used for data cables, another for electrical cable and yet leaving space for future services. Although where there's preexisting trunking, they may make use of it. During the Site Visits for all the 3 sites it was mentioned that we don't need the metallic trunking to run the data and electrical cables as there is provision on the wall for data points and electrical points. Information given during the site visit was that the electrical points and data points</p>	02.04.2025	The Metal trunking shall be available in all the areas that you will be required to install the points. They are no longer flash wall mounted. The Metal trunking shall only be needed where one shall be crossing cables from one half of the building to the other.	Clarification

	<p>would be wall mounted directly with no need for metallic trunking.</p> <p>Kindly clarify is this is still the position on the metal trunkings"</p>			
23	<p>"7.0 Structured Cabling</p> <p>Data outlets shall be flash mounted on the metal trunking. During the Site Visits for all the 3 sites it was mentioned that we don't need the metallic trunking to run the data and electrical cables as there is provision on the wall for data points and electrical points.</p> <p>Information given during the site visit was that the electrical points and data points would be wall mounted directly with no need for metallic trunking.</p> <p>Kindly clarify is this is still the position on the metal trunkings"</p>	02.04.2025	<p>The Metal trunking shall be available in all the areas that you will be required to install the points. They are no longer flash wall mounted. The Metal trunking shall only be needed where one shall be crossing cables from one half of the building to the other.</p>	Clarification
24	<p>"7.0 Structured Cabling</p> <p>The horizontal cabling will include outlets and consolidation or transition points, connectors, mechanical terminations and patch cords that compose horizontal cross-connect. Cables will be routed in new wall ducts and terminated on patch panels and other data outlets as specified in accompanying diagrams.</p>	02.04.2025	<p>The site diagrams were shared through the emails provided during the registration of interest bidders.</p>	Clarification

	Kindly share the site diagrams for this tender as promised during the site visit"			
25	Please confirm if the above tender is for AGPO or Open to all Contractors.	03.04.2025	This is an open Tender to all bidders.	Clarification
26	<p><b>Clarification regarding lot 1 on the following key issues.</b></p> <p>You were supposed to share the drawings related to Lot 1 and 2 that are separate from the shared electrical layouts within the week which we are yet to receive.</p> <p>In lot 1 in your BOQ you have left behind trunking for data and fiber optic cable to connect the buildings, would you kindly clarify if it's the bidder who will supply the Fiber optic cable its mode (single or multimode) and install for lot 1.</p> <p>For data and power trunking, is it being done by the contractor on site who was installing the cable trays or the bidder to quote them?</p>	03.04.2025	<p>Q1. The drawings provided included markings for all the datapoints, Wi-Fi access points and CCTV cameras as promised. Please follow the supply schedule as in the bid document.</p> <p>Q2. Bidder to supply the fiber optics cable. Please refer to the bidding document.</p> <p>Q3. The Metal trunking shall only be needed where one shall be crossing cables from one half of the building to the other. And from where the backhaul radios data cable shall be routed into the building.</p>	Clarification
	- ends -			